



# QUOTE

ALL HALLOWS CHURCH BRISTOL  
All Hallows Road  
Bristol  
Bristol, City Of  
BS5 0HH  
GBR

**Date**  
5 Feb 2026

**Expiry**  
28 Feb 2026

**Quote Number**  
QU-1398

**Reference**  
SAMUEL FORD

**VAT Number**  
469516355

Connect Infrared Limited  
No 1 St Pauls Square  
Birmingham  
B3 1QU  
UNITED KINGDOM

## SECOND DRAFT - FULL CHURCH HEATING - INCLUDES NEW ROOM

SITE VISIT CARRIED OUT BY KEVIN AND GLENN WITH SAM FROM THE CHURCH. TUESDAY 3RD FEBRUARY 2026

THE NEW CONFIGURATION IS AS PER THE BELOW QUOTE WHICH INCLUDES SPECTRUM HEATERS, PEW HEATERS AND PANEL HEATERS

CONNECT INFRARED PROVIDE A MANAGED HEATING SERVICE. FROM DESIGN, QUOTE TO FINAL INSTALLATION AND SUPPORT SERVICE

WE OFFER SERVICE TO ENSURE YOU ARE COMFORTABLE WITH YOUR NEW HEATING SYSTEM AND AFTER CARE PROVIDED BY US: -

### 1. Fabric-First System Design

We start with a fabric-first approach — assessing insulation, building fabric, and efficiency before designing a tailored heating solution for optimal performance and comfort.

### 2. Heater Specification & Placement

Expert selection and precise positioning of heaters to ensure even warmth, efficiency, and visual harmony within your space.

### 3. Smart Control Integration

Bespoke control systems designed to optimize energy use, reduce costs, and simplify day-to-day operation.

### 4. Net Zero System Evaluation

Comprehensive review of existing heating systems to ensure the new design aligns with your net zero and sustainability objectives.

### 5. On-Site & Drone Assessment

Detailed ground and aerial surveys — including drone imaging for roofs and hard-to-reach areas — to support accurate planning and design.

### 6. Professional Installation Quotes

Coordination of quotations from vetted contractors experienced in church and heritage heating installations.

### 7. Design Plans & Faculty Support Documentation

Preparation of design drawings, specifications, and supporting reports to assist with the Faculty approval process and ensure a smooth path to project approval.

### 8. Project & Site Supervision

End-to-end oversight of installation, maintaining quality, safety, and compliance at every stage.

### 9. Commissioning & User Training

Full system commissioning, testing, and tailored training to help you operate your new system confidently.

### 10. Three-Month Aftercare & Monitoring Review

Follow-up review after installation to monitor system performance, ensuring heating zones operate effectively for church services, activities, and congregation comfort.

Description	Quantity	Unit Price	VAT	Amount GBP
CONNECT INFRARED FIVE STEP APPROACH IS DESIGNED TO PROVIDE A PROJECT MANAGED EFFECTIVE AND EFFICIENT HEATING SOLUTION	0.00	0.00		0.00
WE PROVIDE A CONSULTATIVE APPROACH, MANAGE EACH STEP OF THE WAY AND SUPPLY OUR HEATING PRODUCTS WITH CONTROLS				
THIS DESIGN IS PROVIDED AND ATTACHED & SHOULD BE READ IN CONJUNCTION WITH THIS QUOTE.				
THE DESIGN AND CONFIGURATION IS AS BELOW	1.00	24,200.00	20%	24,200.00
<p>MAIN NAVE AREA: -</p> <p>6 X 4.5KW CONNECT SPECTRUM HEATERS</p> <p>3 HEATERS INSTALLED IN THE TWO SIDE AISLES ON THE CEILING BEAM AT A HEIGHT OF 6.5 METRES DIRECTED TOWARDS THE NAVE.</p> <p>THE DISTANCE FROM THE BEAM TO THE CENTRE OF THE NAVE IS 7.8 METRES WHICH IS WELL WITHIN THE CAPABILITIES OF THE 4.5 KW HEATER.</p> <p>CHANCEL AREA: -</p> <p>THREE 4.5KW CONNECT SPECTRUM HEATERS DIRECTED ONTO THE MAIN CHANCEL AREA.</p> <p>HEATER 1 - THIS WOULD BE POSITIONED ON THE WALL OF THE VESTRY AREA AT 6.5 METRES FACING TOWARDS THE CHANCEL</p> <p>HEATER 2 &amp; 3 - THESE WOULD BE POSITIONED ON THE LADY CHAPEL WALL AT 6.5 METRES FACING TOWARDS THE CHANCEL</p> <p>THE DISTANCE FROM THE OUTER WALLS TO THE CENTRE OF THE CHANCEL IS 8 METRES WHICH IS WELL WITHIN THE CAPABILITIES OF THE 4.5 KW HEATER.</p> <p>TO SUPPLEMENT THE CHANCEL HEAT 6 X 400WATT CHANCEL PEW HEATERS WILL BE INSTALLED IN THE PEWS OF THE CHANCEL.</p> <p>LADY CHAPEL AREA: -</p> <p>1 X CONNECT SPECTRUM 4.5KW HEATER POSITIONED ABOVE THE ARCH WHICH ADJOINS THE SIDE AISLE AT A HEIGHT 6 METRES DIRECTED TOWARDS THE SEATING AREA.</p>				

Description	Quantity	Unit Price	VAT	Amount GBP
-------------	----------	------------	-----	------------

LADY CHAPEL ALTAR: -

1 X CONNECT SPECTRUM 3KW HEATER POSITION ON THE EXTERNAL WALL IN THE ALTAR AREA ON THE BEAM AT 6.6 METRES DIRECTED TOWARDS THE ALTAR.

VESTRY / CHANGING AREA ADJOINING CHANCEL: -

2 X CONNECT 800 WATT PANEL HEATERS - BROWN IN COLOUR MOUNTED UNDER THE ORGAN AREA ON CHAINS TO A HEIGHT OF 2.5 METRES.

VESTRY HALL: -

4 X CONNECT SPECTRUM 3KW HEATERS POSITION ED ON THE CEILING - 2 ON END BEAMS AND 2 ON THE TWO INTERNAL BEAMS AT 4.8 METRES

ENTRANCE / FOYRE AREA: -

4 X CONNECT 800 WATT PANEL HEATERS - BROWN IN COLOUR MOUNTED ON THE CEILING ON CHAINS LOWERING TO 2.5 METRES

CONTROLS: -

THIS WOULD BE SIMPLISTIC ON / OFF SWITCHES AS THERE IS NO INTERNET AT THIS PRESENT TIME.

THE ELECTRICIAN WILL PROVIDE THESE SWITCHES AND WE WOULD NEED TO KNOW YOUR PREFERENCE FOR THE ZONING BUT THAT CAN BE CONFIRMED DURING INSTALLATION.

WHAT IS INCLUDED: -

- SITE VISITS,
- DESIGNS & PLACEMENT OF HEATERS
- PROJECT MANAGEMENT,
- ARRANGING AND MANAGING INSTALLATION AND LIAISON WITH THE ELECTRICAL TEAM,
- FULL AFTER CARE SERVICE FOR THREE MONTHS
- 5 YEAR GUARANTEE ON HIGH POWER HEATERS
- 10 YEAR GUARANTEE ON THE PANELS
- 2 YEAR GUARANTEE ON PEW HEATERS

LIST OF PRODUCTS

- 10 X 4.5KW CONNECT SPECTRUM HEATERS - COLOUR TO BE CONFIRMED
- 5 X CONNECT SPECTRUM HEATERS - COLOUR TO BE CONFIRMED
- 6 X CONNECT 800 WATT PANELS
- 6 X 400 WATT UNDER PEW HEATERS

Description	Quantity	Unit Price	VAT	Amount GBP
-------------	----------	------------	-----	------------

PRODUCT BREAK DOWN AND COSTS

4.5 Spectrum x 10 x £1,600 - 10% = £14,400

3kw Spectrum x 5 x £1,050 - 10% = £4,725

800 watt panel heaters x 6 x £560 - 25% = £2,520

400 watt Under pew x 6 x £390 - 10% = £2,106

Site visit + Design and Project management = £450

Total = £24,200 + VAT

Cost is £23,751 + our costs but we've deducted it by the £1.

DELIVERY	1.00	350.00	20%	350.00
INSTALLATION	1.00	20,000.00	20%	20,000.00

THE ELECTRICIAN HAS PROVIDED THE QUOTE OF £20,000

- FOR REMOVAL OF OLD HEATERS & MAKING SAFE

- FOR INSTALLATION OF NEW HEATERS AND CONTROLS,

SCOPE OF WORKS TO INCLUDE,  
 SITE/PROJECT MANAGEMENT  
 REMOVAL OF OLD HEATERS & MAKE SAFE,  
 WIRING,  
 INSTALLATION OF NEW HEATERS,  
 NEW BOARD(S),  
 INSTALL OF CONTROLS & COMMISSION  
 ACCESS EQUIPMENT HIRE

REMOVAL OF HEATERS AS PER: -

Porch: 1 wall mounted heater  
 Narthex (the lobby area): 1 wall mounted heater - Office:  
 1 - Nave: 6 - Aisles: 6 (3 in each) - Chancel: 6 - Vestry: 1 -  
 Lady Chapel: 2 - Hall: 1 fan heater

DISCOUNTS - THIS QUOTE HAS A DISCOUNT OF

10% APPLIED FOR THE CONNECT HIGH POWER HEATERS

25% DISCOUNT ON THE CONNECT PANELS

10% DISCOUNT ON PEW HEATERS

QUOTE TIMESCALE

INSTALLATION DATE PENCILLED IN IS WEEK COMMENCING  
 23RD MARH 2026

THIS QUOTE EXPIRES 28TH FEBRUARY 2026

Description	Quantity	Unit Price	VAT	Amount GBP
-------------	----------	------------	-----	------------

PAYMENT TERMS & CONDITIONS

THE FOLLOWING PAYMENTS TERMS ARE NECESSARY FOR THIS PROJECT: -

1. 75% FOR PRODUCTS PAID ON RECEIPT OF INVOICE -  
 £18,150.00 + VAT = £21,780.00 + DELIVERY £350.00 + VAT  
 = £22,200

2. 25% FOR INSTALLATION COSTS ON RECEIPT OF INVOICE  
 - £5,000.00 + VAT = £6,000.00

3. FINAL 25% FOR PRODUCTS AT TIME OF DELIVERY -  
 £6,050.00 + VAT = £7,260.00

4. FINAL 75% PAYMENT FOR INSTALLATION ON  
 COMPLETION OF THE INSTALL - £15,000.00 + VAT =  
 £18,000

COLOUR - WE CAN DECIDE ON A COLOUR TO SUIT THE ENVIRONMENT

WE CAN OFFER A RAL COLOUR OF YOUR CHOICE - TO BE DISCUSSED

Subtotal	44,550.00
TOTAL VAT 20%	8,910.00
<b>TOTAL GBP</b>	<b>53,460.00</b>

**Terms**

This document has been produced exclusively for your premises and is strictly confidential. It is not to be shared, distributed, or circulated to any third party without prior authorisation.

Full payment of the order value is required. Payment is required on orders before dispatch. Connect Infrared will advise on the delivery date once full payment has been received. Cheque Payment are not accepted.

Heating requirements are based on the assessment of your property and any information provided to Connect Infrared.

Connect Infrared cannot be held responsible if your heating requirements have not been met if all information has not been supplied correctly or advice from Connect Infrared has been disregarded. Connect Infrared cannot be held liable for any damage caused to property by equipment or installation. By accepting the quote or invoice you are agreeing to these terms.

Please see a list of our terms and conditions on our website [www.connectinfrared.co.uk](http://www.connectinfrared.co.uk)

Connect Infrared Limited  
 Office 49, 42 Broadwell Road,  
 Oldbury,  
 West Midlands  
 B69 4BY  
 VAT No. 469516355